

Vertical Autoclave Hospital Model

Technical Data: Triple Wall Construction, made up of SS304 Working

Temperature 121°C @pressure 15 PSI, Foot lifting lid.

Fully Automatic Operated

- 1) High temperature Joint less silicon gasket
- 2) I.S.I. Mark SS Heater
- 3) Digital Screen Display
- 4) Settable log/sterilization time interval.
- 5) Adjustable Soak Time in 1 min to 99 min.
- 6) Low water level switch for heater protection
- 7) Automatic Steam controlling in chamber, temp maintaining, sterilization time holding, Auto-Exhaust, Cycle end.

Dimension	Working Capacity	Manual Operated	Semi-Automatic Operated	Fully Automatic Operated
12" x 20"	37 Liters	VMT1220	VST1220	VFT1220
16" x 24"	80 Liters	VMT1624	VST1624	VFT1624

